

MDC-1 POS CABINET

Leviton Cable Manager,
1U, part# 49253-LPM

POS Backbone, (1)
36strand SM Fiber,
Systimax Panel Kit part#
760155739, Fiber
Modules Not Included

POS Backbone, (24)
CAT6, Systimax Patch
Panel part# 760152561


Tenant #1-Typical Demarc
Tie, (1) 24strand SM
Fiber, (12) CAT6

CAT6A Horizontal Cabling,
POS WIFI, Systimax part#
760152587

CAT6 Horizontal Cabling,
POS Proprietary, Systimax
part# 760152561

Switch Space-
Models to Vary

Horizontal Power Supply,
Models To Vary




MDC-2 TENANT CABINET

Leviton Cable Manager,
1U, part# 49253-LPM

Tenant #1-Typical
Demarc Tie, (1) 24strand
SM Fiber, (12) CAT6

Horizontal Cabling,
Tenant Proprietary,
Panel Kit part#
760155747, CAT6/6A
Modules Not Included

Horizontal Power
Supply, Models To Vary



FILENAME

MDC LAYOUT- POS & TENANT CABINETS